





# **FPS 100 SPECIFICATIONS:**

**PRODUCTION SPEED** LOAD SIZE WEIGHT CAPACITY STRUCTURAL TURNTABLE DRIVE

TURNTABLE SPEED CARRIAGE DRIVE FILM DELIVERY FILM ROLL

**OPTIONS** 

1-25 LPH\* 55"L x 55"W x 84"H (80" Diagonal) 5000LBS WELDED STEEL CONSTRUCTION 1/2HP SCR DRIVE, 20:1 GEARBOX 32 TABLE SUPPORT WHEELS 0-15RPM MANUAL LIFT CARRIAGE TENSION STRETCH 18" HAND FILM POWER REQUIREMENTS 115VAC, 15A, 60Hz- PLUG AND PLAY

> LOADING RAMP COMBINATION RAMP- FOR POWERED HAND TRUCKS

\*Loads Per Hour- May vary depending on load sizes, loading/unloading speeds, and number of wraps or wrapping pauses on load.



# **FULL SPECIFICATIONS:**

#### **CONTROL FEATURES:**

Power On/Off switch

Soft Start/Stop DC drive

 Variable Turntable Speed 0-15 RPM

• All circuits protected by fuses (easy access)

## **FILM DELIVERY SYSTEM:**

- Manual Lift Carriage
- Hand tensioner provides some stretch No hinges, latches or idler rollers to wear and
- cause inconsistent film stretching

### **CARRIAGE LIFT:**

• UHMW supports providing effortless movement and maximum stability (Qty4)

- Counterweight balanced
- #50 ANSI chain

#### **TURNTABLE DRIVE:**

- 0–15 RPM Table Speed
- 1/2 HP SCR variable speed
- Adjustable electronic soft start / stop
- · 32 table support wheels