





## **FPS 150 SPECIFICATIONS:**

# **FULL SPECIFICATIONS:**

### **CONTROL FEATURES:**

- Simply Set Control Panel
- Variable Turntable Speed 0-15 RPM
- Variable Film Carriage Speed Up/Down Control
- Top/Bottom Wrap Selector 1-3
- Flush Mounted Control Panel (built into tower)
- Manual Film Carriage Raise/Lower Control
- Turntable log with Auto Home Alignment
- Large Emergency push button power On / Off Switch with indicator light
- Start Cycle Push Button
- Standard Wrap Up/Down Program
- 12 Volt DC Control System (for operator safety)
- All circuits protected by fuses (easy access)
- · 20 amp Power Board Circuits to carry a 10 amp load

## **FILM DELIVERY SYSTEM:**

- SPRING LOAD© "dynamic" non-prestretch film delivery system
- 100% + film stretch
- Easy thread film carriage
- · No hinges, latches or idler rollers to wear and cause inconsistent film stretching
- Adjustable mechanical force to load
- · Auto height eye capable of recognizing all colors

#### CARRIAGE LIFT:

· UHMW supports providing effortless movement and maximum stability (Otv4)

- Heavy duty ANSI #50 chain carriage lift
- 1/2 HP DC SCR variable speed drive
- Carriage chain fully guarded

#### **TURNTABLE DRIVE:**

- 0-15 RPM Table Speed
- 1/2 HP SCR variable speed
- · Adjustable electronic soft start / stop
- 32 table support wheels