





## **FULL SPECIFICATIONS:**

### **CONTROL FEATURES:**

- PLC full color touch screen display
- · LCD Display Screen (providing function control viewing)
- · Variable Turntable Speed 0-15 RPM
- Variable Film Carriage Speed Up/Down Control
- Separate Top/Bottom Wrap Selectors 1-9
- · Separate Film Height Selector 1-9"
- Flush Mounted Control Panel (built into tower)
- · Cycle Counter
- Manual Carriage Raise/Lower Control
- Turntable Jog with Auto Home Alignment
- Large Emergency push button power On / Off Switch with indicator light
- Start Cycle Push Button
- · Standard Wrap Up/Down Program
- 12 Volt DC Control System (for operator safety)
- All circuits protected by fuses (easy access)
- · 20 amp Power Board Circuits to carry a 10 amp load

### **FILM DELIVERY SYSTEM:**

- SPRING LOAD "dynamic" non-prestretch film delivery system
- · 100% + film stretch
- Easy thread film carriage
- No hinges, latches or idler rollers to wear and cause inconsistent film stretching
- Electronic film force control on
- · Adjustable mechanical force to load
- Linear analog proximity sensor film feed speed control
- 1/2 HP DC SCR variable speed film
- Triple beam auto height eye capable of recognizing all colors including black

### **CARRIAGE LIFT:**

- UHMW supports providing effortless movement and maximum stability (Qty4)
- · Heavy duty ANSI #50 chain carriage lift
- 1/2 HP DC SCR variable speed drive
- · Carriage chain fully guarded

# TURNTABLE DRIVE:

- 0–15 RPM Table Speed
- 1/2 HP SCR variable speed
- · Adjustable electronic soft start / stop
- Positive home position alignment
- · Safety E-Stop button
- · 32 table support wheels