





FULL SPECIFICATIONS:

CONTROL FEATURES:

- PLC Controls
- LCD Display Screen (providing function control viewing)
- Variable Turntable Speed 0-15 RPM
- Variable Film Carriage Speed Up/Down Control
- · Seperate Top/Bottom Wrap Selectors 1-9
- Seperate Film Height Selector 1-9
- Flush Mounted Control Panel (built into tower)
 Cycle Counter
- Manual Carriage Raise/Lower Control
- Turntable Jog with Auto Home Alignment

 Large Emergency push button power On / Off Switch with indicator light

- Start Cycle Push Button
- 4 different onboard wrap programs
- 12 Volt DC Control System (for operator safety)
- All circuits protected by fuses (easy access)
- 20 amp Power Board Circuits to carry a 10 amp load

FILM DELIVERY SYSTEM:

• HURRICANE THREAD 20" prestretch film delivery system

- 200% factory set stretch (50-250% available upon request)
- Easy thread film carriage

• No hinges, latches or idler rollers to wear and cause inconsistent film stretching

- Electronic film force control on panel
- Adjustable mechanical force to load

• Linear analog proximity sensor film feed speed control

• 1/2 HP DC SCR variable speed film drive

• Triple beam auto height eye capable of recognizing all colors including black

CARRIAGE LIFT:

• UHMW supports providing effortless movement and maximum stability (Qty4)

- Heavy duty ANSI #50 chain carriage lift
- 1/2 HP DC SCR variable speed drive
- Carriage chain fully guarded

TURNTABLE DRIVE:

- 0–15 RPM Table Speed
- · 1/2 HP SCR variable speed
- Adjustable electronic soft start / stop
- Positive home position alignment
- Safety E-Stop button
- · 40 table support wheels